

Demo Concrete Co.

mondogaglione@hotmail.com

QUOTE

Quote # **135AC343**
Date **June 16, 2026**
Valid for **30 days**

PREPARED FOR

Thank you for the opportunity to quote your project.

Itemized pricing

Description	Qty	Unit	Unit price	Total
Ready-mix concrete 30 MPa 1830 sq ft @ 4" (incl. 10% waste)	19.25	m3	\$313.33	\$6,031.67
Granular A 4" compacted base (incl. 10% waste)	42	tonne	\$42.67	\$1,792.00
Wire mesh 6x6 W2.9 (incl. 10% waste)	2013	sqft	\$0.37	\$751.52
Poly vapour barrier 6 mil (incl. 10% waste)	2013	sqft	\$0.11	\$214.72
Foreman x 1 3 days	24	hr	\$53.33	\$1,280.00
Finisher x 1 3 days	24	hr	\$53.33	\$1,280.00
Labourer x 2 3 days	48	hr	\$53.33	\$2,560.00
Excavator 2 days incl. mobilization	2	day	\$1,033.34	\$2,066.67
Skid steer 3 days incl. mobilization	3	day	\$533.33	\$1,600.00
Plate tamper 3 days incl. mobilization	3	day	\$120.00	\$360.00
Power trowel 1 day incl. mobilization	1	day	\$240.00	\$240.00
Excavated soil disposal 43.2 m ³ loose in 14 yd bins	5	bin	\$733.33	\$3,666.66
			Subtotal	\$21,843.24
			Tax (13%)	\$2,839.62
			Total	\$24,682.86

Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

Thank you for your business.

Questions? mondogaglione@hotmail.com

Demo Concrete Co.