

Demo Concrete Co.

mondogaglione@hotmail.com

QUOTE

Quote # **135AC343**
Date **June 16, 2026**
Valid for **30 days**

PREPARED FOR

Thank you for the opportunity to quote your project.

Included in this quote

MATERIALS

Ready-mix concrete 30 MPa 1830 sq ft @ 4" (incl. 10% waste)	19.25 m3
Granular A 4" compacted base (incl. 10% waste)	42 tonne
Wire mesh 6x6 W2.9 (incl. 10% waste)	2013 sqft
Poly vapour barrier 6 mil (incl. 10% waste)	2013 sqft

LABOUR

Foreman x 1 3 days	24 hr
Finisher x 1 3 days	24 hr
Labourer x 2 3 days	48 hr

EQUIPMENT

Excavator 2 days incl. mobilization	2 day
Skid steer 3 days incl. mobilization	3 day
Plate tamper 3 days incl. mobilization	3 day
Power trowel 1 day incl. mobilization	1 day

DISPOSAL

Excavated soil disposal 43.2 m ³ loose in 14 yd bins	5 bin
---	-------

Subtotal	\$21,843.24
Tax (13%)	\$2,839.62

Total

\$24,682.86

Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

Thank you for your business.

Questions? mondogaglione@hotmail.com

Demo Concrete Co.