

Demo Concrete Co.

mondogaglione@hotmail.com

QUOTE

Quote # **C42812C6**
Date **June 16, 2026**
Valid for **30 days**

PREPARED FOR

Thank you for the opportunity to quote your project.

Included in this quote

MATERIALS

Ready-mix concrete 30 MPa 1.5 m3
100 sq ft @ 5" (incl. 10% waste)

Granular A 2.5 tonne
4" compacted base (incl. 10% waste)

Wire mesh 6x6 W2.9 (incl. 10% waste) 110 sqft

LABOUR

Foreman x 1 8 hr
1 day

Finisher x 1 8 hr
1 day

Labourer x 2 16 hr
1 day

EQUIPMENT

Excavator 1 day
1 day incl. mobilization

Skid steer 1 day
1 day incl. mobilization

Plate tamper 1 day
1 day incl. mobilization

Power trowel 1 day
1 day incl. mobilization

DISPOSAL

Excavated soil disposal 1 bin
2.7 m³ loose in 14 yd bins

Subtotal \$5,284.40

Tax (13%) \$686.97

Total \$5,971.37

Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

Thank you for your business.

Questions? mondogaglione@hotmail.com

Demo Concrete Co.